

INVITATION TO TENDER

NEELI MOSQUE

Supply & Installation — Floor Finishes Package

Project	Neeli Mosque
Site Address	Hare St, Rochdale OL 11 1JL
Issuing Contractor	Meridian Construction & Refurbishment Ltd
Package Reference	MCR-FF-XXX-TP-001
Document Issue Date	[INSERT DATE]
Tender Return Date	[INSERT DATE] — 12:00 noon
Tender Validity	12 weeks from Tender Return Date
Contact for Queries	[INSERT NAME / EMAIL / TEL]

STRICTLY PRIVATE & CONFIDENTIAL — ISSUED FOR TENDERING PURPOSES ONLY

This document is commercially sensitive. Recipients must not copy or distribute without the written consent of Meridian Construction & Refurbishment Ltd.

Contents

INVITATION TO TENDER.....	4
1.1 Issuing Party	4
1.2 Scope Summary.....	4
1.3 Contract Particulars.....	4
1.4 Tender Basis	4
1.5 Tender Queries	4
SCOPE OF WORKS.....	5
2.1 Works Included	5
2.2 Works Excluded	5
SYSTEM & PRODUCT DESCRIPTION	6
3.1 Floor Finish Types & Tender Quantities	6
3.2 Entrance Matting Systems	6
3.3 Threshold & Transition Systems	6
TECHNICAL REQUIREMENTS	7
4.1 General Compliance	7
4.2 Substrate Acceptance	7
4.3 Installation and Finish	7
4.4 Threshold Accessibility Requirements	8
PERFORMANCE REQUIREMENTS.....	9
5.1 Performance.....	9
5.2 Inspection and Test Plan	9
5.3 Workmanship and Protection	9
QUANTITIES, ALLOWANCES & PRICING RULES	10
6.1 Measurement Status	10
6.2 Separately Identified Allowances	10
INTERFACES & COORDINATION	11
7.1 Key Interfaces	11
7.2 Setting Out and Tolerances	11
QUALITY CONTROL.....	12
8.1 Pre-Installation Submissions.....	12
8.2 Handover Documentation	12
HEALTH & SAFETY	13
9.1 General Obligations	13
9.2 Key Risks and Controls.....	13
PROGRAMME.....	14
10.1 Key Dates.....	14
10.2 Tender Programme Requirement	14
10.3 Indicative Sequence.....	14
TENDER RETURN REQUIREMENTS.....	15
11.1 Return Address & Deadline	15
11.2 Mandatory Submission Documents	15
11.3 Qualifications & Assumptions	15
PRICING FORMAT.....	16

12.1 Lump-Sum Pricing Schedule	16
12.2 Schedule of Rates & Daywork	16
DEFECTS LIABILITY	17
13.1 Defects Liability Period	17
13.2 Warranties	17
PAYMENT TERMS	18
14.1 Valuation & Payment	18
14.2 Applications for Payment	18
ASSUMPTIONS/INFORMATION REQUIRED	19
15.1 Information Required Before Tender Issue or Award	19
15.2 Tender Assumptions	19
APPENDICES	20

01 INVITATION TO TENDER

1.1 Issuing Party

Meridian Construction & Refurbishment Ltd (the "Main Contractor") invites suitably qualified and experienced floor-finishes subcontractors to submit a fixed-price tender for the complete supply and installation of the Floor Finishes Package at Neeli Mosque, Rochdale, UK.

1.2 Scope Summary

The package comprises floor preparation, supply, delivery, installation, finishing, protection, testing and handover of epoxy flooring, vinyl flooring, non-slip ceramic tiles, general tile flooring, coarse-textured non-slip tiles, carpet flooring, three-zone entrance matting systems and threshold strips. The tender shall include all labour, materials, accessories, plant, supervision, setting out, samples, wastage, trims and documentation necessary for a complete installation.

1.3 Contract Particulars

Project	Neeli Mosque
Location	Hare St, Rochdale OL 11 1JL
Employer / Main Contractor	Meridian Construction & Refurbishment Ltd
Form of Contract	INSERT — e.g. JCT Standard Building Sub-Contract 2016]
Liquidated & Ascertained Damages	INSERT £ per week]
Retention	5% reducing to 2.5% at Practical Completion
Defects Liability Period	12 months from Practical Completion
Payment Terms Monthly Valuations	30-day payment cycle

1.4 Tender Basis

Tenders shall be submitted as a fixed price lump sum, inclusive of all obligations described herein. Conditional or qualified tenders will not be considered. Any qualifications must be listed separately in the Tenderer's Clarifications Register. The Employer reserves the right to reject any tender without explanation.

1.5 Tender Queries

All queries must be submitted in writing to [INSERT CONTACT NAME] at [INSERT EMAIL] no later than [INSERT DATE]. Responses will be issued to all Tenderers simultaneously. No verbal clarifications shall be binding.

02 SCOPE OF WORKS

2.1 Works Included

The Floor Finishes Contractor shall supply, deliver and install the following, fully priced within the lump sum:

- Verify dimensions, substrate condition, levels, moisture content and interface tolerances before ordering or commencing work
- Prepare substrates by cleaning, local grinding, smoothing, priming, levelling and making good as required for the specified finish; identify major remedial screed work separately
- Supply and install all specified floor finishes, adhesives, primers, underlays, grouts, sealants, movement-joint profiles, edge trims, skirtings/coves where shown, transition pieces and proprietary accessories.
- Set out finishes to approved samples and layouts, maintaining straight joints, balanced cuts, pattern direction and clean junctions
- Provide entrance matting Zones 1, 2 and 3 complete with frames, recess coordination, inserts, fixings and perimeter trims
- Provide all rebated/door thresholds, flat transition/cover strips and ramped thresholds complete with mechanical fixings and compatible sealants
- Protect completed work until handover and replace damaged, stained, loose or defective areas
- Include delivery, unloading, on-site distribution, waste removal, final clean and all attendances necessary for completion
- Provision of all Handover Documentation (O&M Manuals, as-built records, certificates)

2.2 Works Excluded

The following items are expressly outside the scope of this package and will be provided by others unless separately agreed in writing:

- Structural floor construction and wholesale replacement of screeds unless expressly included in the pricing schedule
- Underfloor heating installation, pressure testing and commissioning; the flooring subcontractor remains responsible for coordination and approved heating-up/cooling-down procedures
- Major damp-proofing or structural waterproofing beyond compatible surface primers or membranes expressly specified by the flooring manufacturer
- Removal of unknown hazardous materials
- Furniture, loose rugs and specialist prayer-row markings unless shown in the tender drawings or separately instructed
- Works not evidenced in the issued information shall be identified and separately priced, not assumed

03 SYSTEM & PRODUCT DESCRIPTION

3.1 Floor Finish Types & Tender Quantities

Ref.	Finish	Unit	Tender Quantity	Minimum Tender Requirement
FF-01	Epoxy flooring	m ²	31	Proprietary resin system suitable for the designated use; slip resistance and build-up to be confirmed.
FF-02	Vinyl flooring	m ²	137	Commercial-grade resilient flooring with compatible adhesive; joints and coving to drawings/specification.
FF-03	Non-slip ceramic tiles	m ²	101	Slip-resistant ceramic floor tiles, grout and movement-joint accessories.
FF-04	Tile flooring	m ²	198	Floor tiles to approved sample, including adhesive, grout, cuts and trims.
FF-05	Coarse-textured non-slip tiles	m ²	19	Heavy-duty coarse-textured slip-resistant tiles for designated wet/high-risk areas.
FF-06	Carpet flooring	m ²	430	Commercial/heavy-duty carpet system; mosque carpet pattern, construction and underlay to be confirmed.

Quantities are tender-stage measurement information extracted from the issued schedule. Tenderers shall verify quantities against the drawings and include normal cutting and wastage within their rates.

3.2 Entrance Matting Systems

Ref.	Zone / System	Material Requirement	Unit	Tender Quantity
EM-01	Zone 1 — External scraper	Aluminium system with rubber/brush inserts	m ²	17
EM-02	Zone 2 — Internal barrier	Aluminium system with carpet + scraper inserts (hybrid system)	m ²	22
EM-03	Zone 3 — Internal absorber	Heavy-duty textile barrier matting; nylon/polypropylene carpet tiles or rolls	m ²	21

3.3 Threshold & Transition Systems

Ref.	Threshold Type	Material Requirement	Unit	Tender Quantity
TH-01	Rebated / door threshold	Thermally broken aluminium	m	18
TH-02	Flat transition / cover strip	Anodised aluminium	m	59
TH-03	Ramped threshold	Aluminium ramp strip	m	45

Equivalent totals for pricing reference: TH-01 17.906 m; TH-02 58.730 m; TH-03 44.014 m. Tenderers shall price the stated millimetre quantities and verify lengths, widths and profiles against door/floor interfaces

04 TECHNICAL REQUIREMENTS

4.1 General Compliance

All works and materials shall comply fully with the following regulations, standards and guidance:

- Building Regulations 2010 (as amended), including Approved Documents B, K and M where applicable
- Construction (Design and Management) Regulations 2015
- BS 8203: installation of resilient floor coverings
- BS 5385 series: wall and floor tiling; relevant provisions for floor tiling
- BS 5325: installation of textile floor coverings
- BS 8204 series: screeds, bases and in-situ floorings, as relevant to substrate acceptance and resin flooring
- BS 7976 series / recognised pendulum test methodology for slip resistance, where testing is required
- BS 8300 series: accessible and inclusive design, where applicable
- Manufacturer's current written installation instructions and compatible system warranties

4.2 Substrate Acceptance

- Inspect and record surface regularity, cracks, laitance, contamination, strength, dryness and moisture condition before installation.
- Do not install onto an unsuitable substrate. Notify the Main Contractor immediately and obtain written instruction for remedial work.
- Moisture testing shall follow the floor-finish manufacturer's requirements and relevant British Standards. Record readings by room/area.
- Coordinate floor build-ups so finished levels align with thresholds, drains, doors, lift interfaces and adjoining finishes

4.3 Installation and Finish

- Use a single compatible manufacturer's system wherever practical. Adhesives, primers, levellers, grouts and sealants shall suit the substrate, underfloor heating and service conditions.
- Provide movement joints in the floor finish over structural or screed movement joints; do not bridge active joints.
- Form neat, sealed and accessible changes in level. Profiles shall be securely fixed, flush where practicable and free from sharp edges.
- Wet and entrance areas shall drain correctly without local ponding. Do not obstruct floor drains.
- Mock-ups and samples shall be approved before bulk procurement.

4.4 Threshold Accessibility Requirements

- Threshold height shall be no more than 15 mm, in accordance with the issued requirement referencing Approved Document M.
- Transitions shall be wheelchair accessible, firm, stable and slip-resistant.
- Use anti-slip finishes such as ribbed aluminium where appropriate.
- Use tested fire-rated threshold systems where the door or compartmentation requirement demands compliance with Approved Document B.
- Transitions shall be visible and safe in accordance with the issued requirement referencing Approved Document K

05 PERFORMANCE REQUIREMENTS

5.1 Performance

Element	Required Performance / Evidence
All finishes	Suitable for the intended traffic, cleaning regime, moisture exposure and underfloor-heating conditions.
Slip resistance	Product classification and, where requested, wet/dry pendulum test evidence suitable for the location.
Epoxy flooring	Seamless, fully bonded, chemically and abrasion resistant to manufacturer-declared performance.
Vinyl flooring	Fully bonded, smooth, cleanable and securely welded/sealed where required by area use.
Tiles	Sound, level, well-bonded installation with consistent joints, complete grout coverage and movement accommodation.
Carpet	Commercial durability, dimensional stability, clean seams and pattern alignment; mosque carpet requirements subject to approval.
Entrance matting	Heavy-duty, replaceable inserts; frames flush, secure and compatible with recess and surrounding finishes.
Thresholds	Accessible, slip-resistant, securely fixed, compatible with adjacent finishes and door/fire requirements.

5.2 Inspection and Test Plan

- Hold Point 1 — substrate inspection, moisture results and level survey accepted.
- Hold Point 2 — samples, colour, pattern, batch and setting-out approved.
- Hold Point 3 — first completed area / benchmark installation approved.
- Hold Point 4 — pre-handover inspection, cleaning, protection and defect close-out.
- Provide batch references, test certificates and signed inspection records with handover.

5.3 Workmanship and Protection

Materials shall be stored dry, flat and within the manufacturer's temperature and humidity limits. Completed floors shall be protected using non-staining, vapour-permeable materials where required. Adhesive cure times and trafficking restrictions shall be observed. Any contamination or damage caused by the flooring subcontractor shall be made good at its cost.

06 QUANTITIES, ALLOWANCES & PRICING RULES

6.1 Measurement Status

The quantities in Section 3 are tender quantities derived from the information supplied. They are not a substitute for the tenderer's drawing review. Rates shall include all normal waste, cuts, joints, fixings, consumables, small areas, pattern matching, delivery and installation.

6.2 Separately Identified Allowances

Ref.	Item	Tender Treatment
A-01	Major substrate repairs / screed replacement	State exclusion and provide separately priced schedule of rates.
A-02	Moisture-suppression system	Separately price per m ² , subject to confirmed moisture results.
A-03	Coved skirting / hygienic upstands	Price only where shown; otherwise provide optional rate per linear metre.
A-04	Flooring removal and disposal	Confirm whether included; provide separate rates by finish type.
A-05	Out-of-hours working / phased remobilisation	Identify separately if required by programme.
A-06	Provisional sums	None confirmed; do not insert unapproved provisional sums.

07 INTERFACES & COORDINATION

7.1 Key Interfaces

Interface	Flooring Contractor Responsibility
Screeding / substrate contractor	Agree tolerances, curing, moisture condition, joints and remedial responsibilities before acceptance.
UFH / mechanical contractor	Obtain commissioning status and heating protocol; use compatible products and observe temperature limits.
Door / joinery contractor	Coordinate clearances, thresholds, door swings, frames and finished floor levels.
Tiling / sanitary contractor	Coordinate floor drains, falls, waterproofing terminations and sealant junctions.
Electrical contractor	Coordinate floor outlets and avoid covering access panels or service points.
Decorator / fit-out trades	Agree installation sequence and protection of completed finishes.
Main Contractor	Confirm work areas, logistics, storage, access, samples, setting-out and inspection hold points.

7.2 Setting Out and Tolerances

The subcontractor shall take site dimensions and set out all finishes before procurement. Conflicts between measured dimensions, finish layouts, mat recesses, thresholds and drawings shall be raised before work proceeds. Finished junctions shall be flush or formed with an approved accessible transition.

08 QUALITY CONTROL

8.1 Pre-Installation Submissions

No works shall commence until the following documents have been submitted to and approved in writing by Meridian Construction & Refurbishment Ltd:

- Product data sheets, samples, colours, patterns and finish boards for every floor type.
- Technical data for adhesives, primers, membranes, levelling compounds, grouts, sealants, matting frames and threshold profiles.
- Installation drawings / setting-out plans including seams, tile joints, carpet direction, entrance mat zones, transitions and movement joints.
- Substrate survey, moisture-testing proposal and remedial-work methodology.
- RAMS, COSHH assessments, programme, Inspection and Test Plan and quality checklists.
- Evidence of installer competence and relevant comparable project experience.
- Warranties, slip-resistance evidence, fire classification and sustainability information where applicable.

8.2 Handover Documentation

On completion, the following shall be provided to Meridian Construction & Refurbishment Ltd:

- O&M manual in searchable electronic PDF format.
- As-built floor-finish layouts and product/batch schedule.
- Inspection, moisture and test records; signed defect close-out.
- Manufacturer and installer warranties.
- Cleaning, maintenance, stain-removal and replacement instructions.
- Attic stock / spares: proposed quantities for each finish, clearly stated and separately priced pending confirmation.

09

HEALTH & SAFETY**9.1 General Obligations**

All works shall be carried out in full compliance with the Health and Safety at Work etc. Act 1974, the Management of Health and Safety at Work Regulations 1999 and the Construction (Design and Management) Regulations 2015. The subcontractor shall provide competent supervision, suitable insurances and task-specific controls.

9.2 Key Risks and Controls

- Dust and silica from tile cutting or grinding — use extraction, wet cutting where suitable and correct RPE.
- Solvents, resins, primers, adhesives and cleaning agents — provide COSHH assessments, ventilation and controlled storage.
- Manual handling of rolls, tiles, resin components and matting frames — use planned handling and mechanical aids.
- Noise and flying particles from preparation and cutting — segregate work and use suitable PPE.
- Slips, trips and restricted access during curing — barrier and sign all work areas.
- Fire risk from flammable products or hot works — avoid where possible; use permits and fire controls where required.
- Interface with worshippers or occupied areas — occupancy status and phasing to be confirmed before start.

10 PROGRAMME

10.1 Key Dates

Milestone	Date
Tender return	[INFORMATION REQUIRED]
Subcontract award	[INFORMATION REQUIRED]
Samples / technical submissions	[INFORMATION REQUIRED]
Site access / substrate surveys	[INFORMATION REQUIRED]
Installation commencement	[INFORMATION REQUIRED]
Practical Completion	[INFORMATION REQUIRED]
O&M and warranty handover	No later than Practical Completion

10.2 Tender Programme Requirement

Submit a detailed procurement and installation programme showing technical approvals, samples, lead times, substrate surveys, phased deliveries, installation by floor/area, curing periods, protection and handover. Identify long-lead items and proposed mitigation.

10.3 Indicative Sequence

- Approve products, samples, layouts and interface details.
- Complete substrate survey, moisture testing and remedial works.
- Coordinate UFH commissioning and environmental conditions.
- Install wet-area / tiled finishes and resin systems as programme requires.
- Install vinyl and carpet after dusty and wet trades are complete.
- Install entrance matting and thresholds in coordination with final levels and doors.
- Inspect, protect, clean, rectify and hand over.

11 TENDER RETURN REQUIREMENTS

11.1 Return Address & Deadline

Tenders must be returned to [INSERT NAME / EMAIL] by [INSERT DATE] at 12:00 noon. Late submissions will not be considered.

11.2 Mandatory Submission Documents

The following must be included. Tenders missing mandatory items will be deemed non-compliant:

#	Document / Item	Status
1	Completed Pricing Schedule in Section 12 format	MANDATORY
2	Product schedule with manufacturers, references, finishes and technical data	MANDATORY
3	Detailed programme, lead times and proposed phasing	MANDATORY
4	Clarifications, exclusions and assumptions register	MANDATORY
5	Substrate preparation and moisture-testing methodology	MANDATORY
6	Sample and approval schedule	MANDATORY
7	RAMS / outline H&S submission and COSHH approach	MANDATORY
8	Insurance and installer competency evidence	MANDATORY
9	Warranties and performance evidence	MANDATORY
10	Comparable project experience and references	MANDATORY
11	Value engineering options, separately priced	OPTIONAL

11.3 Qualifications & Assumptions

No assumption embedded in a rate will be valid unless separately declared. All qualifications and exclusions shall be listed in the tender return. The Main Contractor may reject a materially incomplete or qualified tender.

12 PRICING FORMAT

12.1 Lump-Sum Pricing Schedule

Ref.	Cost Heading	Qty / Basis	Amount (£)	Notes
A	Preliminaries, supervision, logistics, protection and waste	Lump sum	£	
B1	Epoxy flooring	30.07 m ²	£	
B2	Vinyl flooring	136.62 m ²	£	
B3	Non-slip ceramic tiles	100.95 m ²	£	
B4	Tile flooring	197.20 m ²	£	
B5	Coarse-textured non-slip tiles	18.27 m ²	£	
B6	Carpet flooring	429.85 m ²	£	
C1	Entrance matting — Zone 1 external scraper	16.42 m ²	£	
C2	Entrance matting — Zone 2 internal barrier	21.79 m ²	£	
C3	Entrance matting — Zone 3 internal absorber	20.81 m ²	£	
D1	Rebated / door thresholds	17,905.72 mm	£	
D2	Flat transition / cover strips	58,729.89 mm	£	
D3	Ramped thresholds	44,013.66 mm	£	
E	Testing, samples, certification and handover	Lump sum	£	
F	Overheads and profit	% / Lump sum	£	
	TOTAL LUMP SUM (EXCL. VAT)		£	

12.2 Schedule of Rates & Daywork

Item	Unit	Rate
Skilled flooring operative	hour	£
Labourer	hour	£
Working foreman	hour	£
Material addition on net cost	%	
Small tools / plant addition	%	
Substrate smoothing / levelling compound	m ²	£
Moisture-suppression system	m ²	£
Floor finish removal by type	m ²	£
Additional aluminium transition profile	m	£

13 DEFECTS LIABILITY

13.1 Defects Liability Period

The Defects Liability Period (DLP) shall be 12 months from Practical Completion. The subcontractor shall promptly rectify defects in materials, preparation, adhesion, joints, pattern, thresholds, matting, workmanship or protection at no additional cost to Meridian Construction & Refurbishment Ltd.

13.2 Warranties

- Provide the maximum available manufacturer system warranty for each finish; minimum periods are to be confirmed with the product proposals.
- Confirm installer-backed workmanship warranty.
- Warranties shall not be invalidated by using incompatible primers, adhesives, levellers, grouts or cleaning products.
- State exclusions, maintenance conditions and commencement dates within the tender.

14 PAYMENT TERMS

14.1 Valuation & Payment

Item	Basis
Valuation	Monthly interim valuations against the accepted pricing schedule.
Application cut-off	[INFORMATION REQUIRED]
Payment period	[INFORMATION REQUIRED — to be confirmed in subcontract]
Retention	5% of gross interim valuations; proposed half release at Practical Completion and balance after DLP.
VAT	All tender prices exclusive of VAT.
Contra-charges	Actual cost plus 15% administration for attributable defects, damage, waste, delay or completion by others, subject to contract.

14.2 Applications for Payment

Applications shall be supported by measured progress against the accepted pricing schedule, delivery evidence where applicable and approved variation records. Unapproved materials, stored goods or variations shall not be included.

15

ASSUMPTIONS/INFORMATION REQUIRED**15.1 Information Required Before Tender Issue or Award**

Ref.	Outstanding Information	Required Action
IR-01	Full project postal address, client and consultant details	Main Contractor to confirm.
IR-02	Tender return date, query deadline and contact details	Insert before issue.
IR-03	Subcontract form, payment period, LADs, cut-off date and final retention terms	Confirm commercial particulars.
IR-04	Latest floor-finish drawings, room schedule and finish legend	Issue as Appendix A.
IR-05	Detailed product/manufacture specifications, colours, sizes and finish codes	Confirm through design/specification.
IR-06	Carpet construction, mosque prayer-row pattern, pile, colour, underlay and jointing	Client/design approval required.
IR-07	Epoxy system build-up, performance class and designated locations	Confirm specification.
IR-08	Tile sizes, slip classifications, grout, waterproofing and movement-joint details	Confirm specification.
IR-09	Vinyl type, thickness, wear layer, coved skirting and welding requirements	Confirm specification.
IR-10	Entrance mat recess depths, module sizes, frame details and exact locations	Confirm against drawings/site.
IR-11	Threshold profile widths, door/fire ratings and interface details	Coordinate with door schedule and accessibility strategy.
IR-12	Substrate/screed specification, tolerances, moisture status and UFH commissioning protocol	Issue coordinated information.
IR-13	Programme, access, phasing, storage, occupancy and working-hour restrictions	Main Contractor to confirm.
IR-14	Attic stock/spares quantities and O&M copy requirements	Confirm before award.
IR-15	Whether removal of existing finishes and major substrate repairs are included	Define scope and provide quantities.

15.2 Tender Assumptions

- The package is tendered on a supply-and-install basis.
- The quantities in this document are the only verified quantities available from the supplied screenshots.
- No brand, colour, tile size, carpet pattern or resin build-up has been assumed where it was not shown.
- All tenderers must identify deviations and price any optional recommendations separately.
- The latest issued drawings and specifications, once confirmed, shall take precedence over tender-stage summary quantities in the event of a documented discrepancy.

APP**APPENDICES**

The following appendices form part of this Invitation to Tender and, upon contract award, shall form part of the contract documents:

Appendix	Document	Status
A	Floor Finishes Mark-up Drawings / Room Finish Schedule	TO BE ISSUED
B	Entrance Matting and Threshold Mark-ups	TO BE ISSUED
C	Pricing Schedule	INCORPORATED IN SECTION 12
D	Tender Clarifications and Assumptions Register	TENDERER TO SUBMIT
E	Programme / Site Logistics Information	INFORMATION REQUIRED
F	Product Data, Samples and Technical Submittals	TENDERER TO SUBMIT

END OF TENDER DOCUMENT

Neeli Mosque — MCR-FF-XXX-TP-001

Meridian Construction & Refurbishment Ltd | All Queries to: [INSERT EMAIL]